

2018 Roadway Rehabilitation Project

Wedgewood Construction Notice

April 27, 2018



Hotline
(612) 430-2805



Project Email
woodbury2018rehab@bolton-menk.com



InTouch Updates
Every Week

Phase 1 Begins May 14

Work in phase one is scheduled to begin Monday, May 14, and will last for about 4 weeks. Please refer to page two for the phasing location map.

Concrete Removal & Replacement

Curb removal and replacement is anticipated to begin **May 14** and last approximately 1.5 weeks. White arrows have been painted on the curb to show areas for replacement. If a curb section is sunken, heaved, or has large chunks of concrete missing from the gutter line, it typically meets the criteria for removal. Curb that is cracked, but still functional, will not be removed. Please note that new curb cannot be driven over for approximately 5 days following placement. The contractor will not warranty concrete that has been driven on before it has cured.

Street Surface Removal

On **May 25-30**, the contractor will be removing the asphalt street surface. This process will leave a gravel driving surface. The contractor will pave the first layer of new pavement 5-7 days after concrete replacement. A second and final layer of pavement will be placed approximately 1-2 weeks after the first layer. Preparatory work will include raising existing structure covers within the roadway prior to paving the second layer.

Parking

Please do not park on any streets within phase one during construction beginning at 7 a.m. until all work is done for the day. If the curb in front of your driveway is not marked for removal, please park on your driveway at all times.

If curb is marked in front of your driveway for removal, you will lose access to your driveway and may also have a portion of your driveway patched following the curb replacement. Replaced asphalt driveways can be driven over 30 minutes following asphalt placement, and replaced concrete driveways can be driven over approximately 5 days after placement. Please park on the street in front of your house if your driveway is affected until the contractor reopens access to your driveway. Please avoid parking in front of other curb sections marked for replacement, or parking on the street during days of pavement removal.

Irrigation Systems, Invisible Fence, & Landscaping

The curb replacement process will require excavation behind the curb. To protect your private features (irrigation lines and heads, underground dog fences, landscaping, etc.) from the construction, please temporarily remove them from the City owned Right of Way behind the curb pieces marked for removal.

